



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Glen Rupe & Walter Probst.

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name: Herman Well No. 2

Location: NW-SE-SW Sec. 15 Twp. 10 Rge. (E)(W) 24

County: Graham Total Depth 3571 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

NO SURFACE PIPE SET . (7 7/8" Hole).
Top of Dakota section @ 950'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx.
cement thru DP. Pull DP to 250' and circulate cement to bottom of cellar
with 100 Sx.

Very truly yours,

R. L. Nichols
Conservation Division Agent