

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompson of Apex Casing Pulling Co., has this

date requested permission to plug the following described well:

Donald C. Slawson Oil Co.,

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson Oil Company,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Hobbs Well No. A-1

Location: CSW-NW Sec. 19 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3979 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

210' -- 8 5/8" surface pipe, cement circulated with 165 Sx.

3975' -- 4 1/2" production casing cemented with 150 Sx. Top perforations @ 3923.

Sand well back to 3910' and set 5 Sx, cement with dump bailer. Pull 4 1/2" casing to 540' and circulate heavy gel mud. Pull 4 1/2" to 510' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 210' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent