

15-065-20624-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*2* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 24 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt.

Complete Address P. O. Box #370, Hays, Kansas.

Lease Name Manz Well No. 2

Location App C S/2 S/2 NE  
140' FSL and 1320' FEL NE/4 Sec. 24 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4015'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.       

Operation Completed: Hour 1:30 AM Day 22 Month 8 Year 1973

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 110 Cu. Ft. cement  
thru DP from 1100' to 775'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 8/24/73  
INV. NO. 7817-12

Signed: *W. L. Dechels*  
Well Plugging Supervisor