

15-065-20354-0000

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION
AUG 11 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,
Complete Address Drawer #370, Hays, Kansas.
Lease Name Thelma Billings Well No. 1
Location NE-NW-NW Sec. 24 Twp. 10 Rge. (E) (W) 24
County Graham Total Depth 3828'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor L. J. Dreiling & Sons, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 2:00 PM Day 9 Month 8 Year 1970

The above well was plugged as follows:

176'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1120' and displaced 100 Sx. cement thru DP from 1120' to 800'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from 185' to 125'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols

Well Plugging Supervisor

DATE 8/11/70INV. NO. 2365-W