

15-065-20345-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co.,

Complete Address 1425 Wichita Plaza Wichita, Kansas

Lease Name Billings Well No. 1

Location NE NE SW Sec. 25 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4010

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor Co. Tools

Address _____ License No. _____

Operation Completed: Hour 2:30 P Day 4 Month 7 Year 1970

The above well was plugged as follows:

RTD 4010' 8 5/8 csg set at 217' cwc Cmt. Mat. 100 sk reg poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 950' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/7/70
INV. NO. 2179-U