

15-065-20164-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RCVD KCC
09-17-68

Operator's Full Name Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name C. Hanna Well No. 1

Location NE-NW-NE Sec. 29 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 3930'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leo J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.

Operation Completed: Hour 5:00 AM Day 11 Month 9 Year 1968

The Above well was plugged as follows:

153'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 100 Sx. cement thru
DP from 1100' to 775'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 125' . Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9/16/68
INV. NO. 8469-W