

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
2-20-1973
FEB 20 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kimbark Operating Company,

Complete Address 1776 Lincoln, Denver, Colorado. 80203

Lease Name Bernard Well No. 3

Location CNE-NW Sec. 2 Twp. 10 Rge. (E) (W) 25

County Graham Total Depth 4013'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Globe Oil Well Cementing, Incorporated,

Address Box #342, Great Bend, Kansas. License No.

Operation Completed: Hour 1:00 PM Day 10 Month 2 Year 1973

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
4005'--4 1/2" Production casing cemented on bottom with 50 Sx. common cement & 600 Gal. Latex. Top of cement @ 2800'. Tubing stub sanded off @ 3050'. 4 1/2" parted @ 1609'. 4 1/2" has been squeezed @ 1609' with 700 Sx. cement.

Tried to pump in 4 1/2" casing, pressure held @ 1000#. Ran 2" tubing to 1522', tubing stopped. Pulled 2" to 1500' and circulated cement to surface with 140 Cu. Ft. Squeezed annulus between 4 1/2" and hole with 260 Cu. Ft. cement from bottom of cellar to 1140'. Pump-in pressure--100#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/22/73
INV. NO. 9023-U