

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-195-20171-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1971
CONSERVATION DIVISION
Wichita, Kansas
01-08-1971

Operator's Full Name Utica Southern Exploration, Incorporated,

Complete Address 808 Palace Building, Tulsa, Oklahoma.

Lease Name Olson Well No. 1

Location SE-SW-SW Sec. 15 Twp. 12 Rge. (E) (W) 22

County Trego Total Depth 4095'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor L.J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No. _____

Operation Completed: Hour 4:30 PM Day 6 Month 1 Year 1971

The above well was plugged as follows:

228'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 625'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 100 Sx. cement thru DP
from 850' to 525'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from 245' to
170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pehala
Well Plugging Supervisor

DATE 1-8-71

INV. NO. 3180-W