

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-195-00186-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 15 TWP. 12 RGE. 22

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Olsen

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Jays

Total Depth 4103 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement - 5 1/2" at 4095' with
100 sax cement behind.

Filled with chat to 4085', set 4 sax cement with dump bailer,
pulled 3347' 5 1/2", filled hole with mud to 210', set rock bridge
and 15 sax cement, filled with mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED

10-13-1951
OCT 13 1951

CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent

Date 10-10-51

PLUGGING
FILE SEC. 15 T. 12 R. 22
BOOK PAGE 115 LINE 37

F