


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 2 Twp. 10 Rge. 25 E/W
Location as "NE/CNW/SW" or footage from lines
NE SW SW

Lease Owner RAM Petroleum Corporation
Lease Name ROME Well No. 1
Office Address 800 Vickers KSB&T Bldg., Wichita, Kans
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed July 8 19 79
Application for plugging filed (verbally) July 8 19 79
Application for plugging approved (verbally) July 8 19 79
Plugging commenced July 8 19 79
Plugging completed July 8 19 79

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4045'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4045'
Set 1st plug at 1050' with 70 sacks
2nd plug at 560' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 3 sacks.
Cemented with 50/50 posmix, 4% gel.
Plug was down at 6:15 p.m., 07-08-79.

RECEIVED
STATE CORPORATION COMMISSION

JUL 17 1979
7-17-1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 79



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: RAM Petroleum Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: ROME #1
 LOCATION: NE SW SW, Section 2-10-25
 Graham County, Kansas
 SPUD DATE: June 29, 1979
 COMPLETION DATE: July 08, 1979

| | | |
|------|------|--------------------|
| 0 | 315 | Clay and sand |
| 315 | 575 | Shale |
| 575 | 771 | Sand and shale |
| 771 | 1625 | Shale |
| 1625 | 2149 | Shale and sand |
| 2149 | 2184 | Anhydrite |
| 2184 | 2448 | Shale and sand |
| 2448 | 2785 | Shale |
| 2785 | 3720 | Lime and shale |
| 3720 | 3808 | Lime |
| 3808 | 3834 | Lime and shale |
| 3834 | 4045 | Lime |
| | 4045 | Rotary Total Depth |

Spud hole at 12:30 p.m., June 29, 1979. Drilled 575' of 12 1/4" hole. Ran 14 joints of 8-5/8" new 24# casing. Set at 574' with 150 sacks of 60/40 posmix 3% Ca.Cl., 2% gel. followed with 165 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did not circulate. Plug was down at 7:30 a.m., June 30, 1979.

T.D. 4045'. Set 1st plug at 1050' with 70 sacks, 2nd plug at 560' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 3 sacks. Cemented with 50/50 posmix, 4% gel. Plug was down at 6:15 p.m., July 08, 1979.

SAMPLE TOPS:

Anhydrite 2149'
 B/Anhydrite 2184'

RECEIVED
 STATE CORPORATION COMMISSION

JUL 17 1979
 7-17-1979
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Rome #1, NE SW SW, Section 2-10-25, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 16th day of July, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.