

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,543

LEASE NAME ROME

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER ONE
SE-SE-SW
330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 2 TWP. 10 RGE. 25 ~~XXXX~~ (W)

COUNTY GRAHAM

Date Well Completed 4-82

Plugging Commenced 1-31-89

Plugging Completed 1-31-89

LEASE OPERATOR L-K WIRELINE, INC.

ADDRESS P.O. BOX 1188--HAYS, KS 67601

PHONE# (913) 625-6877 OPERATORS LICENSE NO. 5453

Character of Well ABANDONED OIL WELL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JANUARY 1989 (date)

by CARL GOODROW (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? WAS ATTACHED TO PLUGGING APPLCIATION

Producing Formation LANSING/KANSAS-CITY Depth to Top 3755 Bottom 3989 I.D. 4347

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION
5-25-1989
MAY 25 1989

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	257	
				5-1/2	4330	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

PERFS @ 3911-18'. SHOT ANHYDRITE @ 2114' & KIOWA @ 1400'. FLUID LEVEL @ 3000+'. SQUEEZED 5 1/2" CASING WITH 175 SX CEMENT WITH 400# HULLS. MIXED INTO MAX PSI 600#. CLOSE IN PSI 600#. SQUEEZED 8-5/8" WITH 125 SX TO MAX PSI 300#. CLOSE IN PSI 150#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING COMPANY License No. _____

Address RUSSELL, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L-K WIRELINE, INC.

STATE OF KANSAS COUNTY OF ELLIS, ss.

BILL R. LONGPINE, PRESIDENT, L-K WIRELINE, INC. (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bill R. Longpine

(Address) BILL R. LONGPINE, PRESIDENT
L-K WIRELINE, INC., P.O. BOX 1188,
HAYS, KS 67601

SUBSCRIBED AND SWORN TO before me this 24TH day of MAY, 1989

Colleen Payton
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES

Colleen Payton
COLLEEN PAYTON Notary Public

Commission Expires: MAY 2, 1991

15-065-21543-00-00

L-K Wireline

R/A LOG

Filing No. _____

COMPANY HIGH PLAINS OIL EXPLORATION, INC.

WELL ROME #1

FIELD ELRICK

COUNTY GRAHAM STATE KANSAS

LOCATION: SE-SE-SW

SEC 2 TWP 10 RGE 25W

Other Services
SONIC BOND LOG

PERMANENT DATUM GROUND LEVEL ELEV 2468

LOG MEASURED FROM KELLY BUSHING 5 FT. ABOVE PERM. DATUM

DRILLING MEASURED FROM KELLY BUSHING

K.B. 2473

D.F. _____

G.L. 2468

DATE	2-8-82
RUN NO.	ONE
TYPE LOG	GAMMA RAY-CORRELATION
DEPTH-DRILLER	
DEPTH-LOGGER	4311
BOTTOM LOGGED INTERVAL	4310
TOP LOGGED INTERVAL	3450
TYPE FLUID IN HOLE	WATER
SALINITY, PPM CL	
DENSITY	
LEVEL	FULL
MAX. REC. TEMP. DEG. F.	
OPERATING RIG TIME	PORTABLE MAST
RECORDED BY	RANDY K. LONGPINE
WITNESSED BY	

RECEIVED
STATE CORPORATION COMMISSION
11-15-1988
NOV 15 1988

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

BORE-HOLE RECORD				CASING RECORD			
RUN NO.	BIT	FROM	TO	SIZE	WGT.	FROM	TO
ONE	12-1/4	000	257	8-5/8			257
TWO	7-7/8	257	4347	5-1/2			

NOV 15 1988
CONSERVATION DIVISION
Wichita, Kansas