

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,679-0000

LEASE NAME Ruder

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 36 TWP. 10 RGE. 24 (E) or (W)

COUNTY Graham

Date Well Completed 8/4/82

Plugging Commenced 10/7/93

Plugging Completed 10/7/93

LEASE OPERATOR Bowman Oil Company

ADDRESS Box 17 Codell, Ks 67630

PHONE# (913) 434-7202 OPERATORS LICENSE NO. 6931

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/6/93 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation KC Depth to Top 3718 Bottom 3724 T.D. 3960

Show depth and thickness of all water, oil and gas formations.

4250 RTKCC

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
KC	Oil & Water	0	250	8 5/8	250'	none
		0	3960	4 1/2	3960	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Ran 2" tubing to 2000' after perforated well at 1945' and 800'. Cemented with 125 sacks w/ 350# of hulls, pulled tubing to 800' and cemented with 30 sacks, cement circulated. Pulled tubing. Pumped 30 sacks of cement in annulus, hook back up to casing and pumped in 40 sacks of cement at 600#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Inc.

License No. _____
STATE CORPORATION COMMISSION

Address P. O. Box 31 Russell, Ks 67665

RECEIVED
DEC 14 1993

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company

STATE OF Kansas COUNTY OF Rooks, ss.


CONSERVATION DIVISION
Wichita, Kansas

Louis D. Bowman

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Louis D. Bowman

(Address) Box 17 Codell, Ks 67630



BEFORE AND SWORN TO before me this 13th day of December, 19 93

Vesta J. Russell
Notary Public

My Commission Expires: July 17, 1996