

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21510 ^{00 00}
LEASE NAME GEYER 2-35 ^{00 00} Wichita, KS

WELL NUMBER 2

NOTICE: Fill out completely 4950 Ft. from S Section Line
and return to Cons. Div. 3620 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 35 TWP. 10S RGE. 24W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY GRAHAM
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 11/27/81

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 1/8/03
Plugging Completed 1/8/03

The plugging proposal was approved on 1/8/03 (date)
by Dennis Hamill w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation LKC Depth to Top 3802 Bottom 3902OA TD 4040 Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	238	8 5/8	238	0
		production	4038	4 1/2	4038	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Perfed 4 1/2" csg @ 2060 & 900'. RIH w/2 3/8' tbg to 2131'. Pumped 85 sxs SMD cmt & 400# hulls. Pulled tbg to 1019'. Pumped 55 sxs & 150# hulls to circ cmt to sur. TOH w/tbg. Tied onto 4 1/2" csg. Pumped 35 & 150# hulls, max press. 200#. 150# ISIP. Tied onto 8 5/8". Pumped 55 sxs & 50# hulls, 150# max press, 100# ISIP. Well P/A. Witnessed and approved by Dennis Hamel w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Wichita, KS


SUBSCRIBED AND SWORN TO before me this 10th day of Jan. 2003

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/18/03 Form CP-4 Revised 05-88

RECEIVED

FEB 20 2003

KCC WICHITA



15-065-21510-0000

SWIFT SERVICES, INC.

Invoice

PO BOX 466
 NESS CITY, 67560-0466

RECEIVED
 FEB 11 2003

DATE	INVOICE #
1/8/03	5182

BILL TO
Murfin Drilling Co Inc PO Box 130 Hill City, KS 67642

JAN 31 2003

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	2	Geyer	Graham		Oil	Abandoned	Lenny	PTA

PRICE REFERENCE...	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
580	Additional hrs.	2	100.00	200.00T
330	Swift Multi-Density	230	9.50	2,185.00T
275	Cotton Seed Hulls	7	22.00	154.00T
581W	Service Charge Cement	250	1.00	250.00T
583W	Drayage	497	0.75	372.75T
	Subtotal			3,161.75
	Sales Tax		5.30%	167.57

USED FOR
 APPROVED

W/O R/A 36
DK

Account	Unit Rig	W L	No.	Amount	Description
898 36		L	2632	3329 ³²	Plug to ABANDON # 2

Thank you for your business.
 RECEIVED

Total \$3,329.32

FEB 20 2003
 KCC WICHITA



CHARGE TO: *Muffin Dng. Co.*
 ADDRESS:
 CITY, STATE, ZIP CODE: *Hill City Ks*

RECEIVED
 FEB 20 2003
 KCC WICHITA

TICKET No 5182

PAGE 1 OF 1

SERVICE LOCATIONS 1. <i>Hay Ks</i>	WELL/PROJECT NO. 2	LEASE <i>Geyer</i>	COUNTY/PARISH <i>Graham</i>	STATE <i>KS</i>	CITY	DATE <i>1-8-03</i>	OWNER <i>Same</i>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO <i>Muffin</i>	SHIPPED VIA <i>105</i>	DELIVERED TO <i>N.W. Wakeeny</i>	ORDER NO.	
3.	WELL TYPE <i>oil</i>	WELL CATEGORY <i>Abandoned</i>	JOB PURPOSE <i>P.T.A.</i>	WELL PERMIT NO.	WELL LOCATION		
4.	REFERRAL LOCATION	INVOICE INSTRUCTIONS					

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
					MILEAGE <i>same trip see ticket 5181</i> <i>same lease</i>						<i>N A</i>
<i>330</i>					<i>Pump charge 2nd Well Group Plugging</i>		<i>2</i>	<i>HRS</i>		<i>100.00</i>	<i>200.00</i>
<i>275</i>					<i>5MD Cement</i>		<i>230</i>	<i>SKS</i>		<i>9.50</i>	<i>2185.00</i>
<i>581</i>					<i>Hulls</i>		<i>7</i>	<i>SK</i>		<i>22.00</i>	<i>154.00</i>
<i>583</i>					<i>Bulk Service charge</i>		<i>250</i>			<i>1.00</i>	<i>250.00</i>
					<i>Drayage</i>		<i>497</i>		<i>T.M</i>	<i>.75</i>	<i>372.75</i>

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X.
 DATE SIGNED *1-8-03* TIME SIGNED *12:00*
 A.M.
 P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?					<i>3161.75</i>
WE UNDERSTOOD AND MET YOUR NEEDS?					
OUR SERVICE WAS PERFORMED WITHOUT DELAY?					
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	<i>167.57</i>
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	<i>3329.32</i>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND					

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR
Dms

APPROVAL
John Gustner

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 1-8-03 PAGE NO. 1

CUSTOMER *Muegin Dalg.* WELL NO. 2 LEASE *Geyer* JOB TYPE *P.T.A* TICKET NO. 5182

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
								ON LOC
								Tbgat 2131 T.D. 3992 4 1/2 csc
85	1300		47 BB ^c					Pump 85 SKS SMD CMT + 400 # Hulls
	1315							Pull tbg to 10 dg +
55	1335							Pump 55 SKS SMD CMT w/ 150 # Hulls
			30 BB ^c					CMT Circ To Surf
	1345							Pull tbg out of hole
35A								hook up to 8 5/8 + Pump 35 SKS of CMT w/ 50 lbs hulls
35								hook up to 4 1/2 + Pump 35 SKS CMT 200 PSI
								shut in 4 1/2
20A								Hook up to 8 5/8 Pump 20 SKS 150 PSI
	1600							Job complete
								4 1/2 175 SKS CMT 700 # hulls
								8 5/8 55 SKS CMT 700 # hulls

RECEIVED

FEB 20 2003

KCC WICHITA