


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-195-00311-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Trego County, Sec. 15 Twp. 12 Rge. 22 ~~E~~^{XX} (W)
Location as "NE/CNW/SW" or footage from lines SW SE NW
Lease Owner The Carl Todd Drilling Company
Lease Name Nixon Well No. 1
Office Address 404 KFH Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-5 1955
Application for plugging filed 12-5 1955
Application for plugging approved 12-5 1955
Plugging commenced 12-5 1955
Plugging completed 12-5 1955
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4122 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LOG ATTACHED						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 190', set plug with 1 sack hulls, cemented through drill pipe with 20 sacks; filled hole with mud to 40' set plug with 1 sack hulls, cemented to base of cellar with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor company tools
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.


Carl Todd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd

404 KFH Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of December, 1955

My commission expires December 14, 1957



Notary Public. *Martha King*

PLUGGING
FILED SEC 15 T 12 R 22 W
BOOK PAGE 32 LINE 2

12-14-1955
DIVISION

15 195 - 00311 - 00 - 00

THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita, Kansas

#1 Nixon
SW SE NW Section 15-12-22W
Trego County, Kansas

COMMENCED: November 25, 1955
COMPLETED: December 5, 1955

ELEVATION: 2357 Kelly Bushing

CASING RECORD

8-5/8" Spiralweld pipe set at 200'
with 150 sacks cement, 3 sacks CC

TOPS

0 - 35	Surface clay
35 - 100	Sand
100 - 200	Shale and shells
200 - 630	Shale and shells
630 - 700	Sand and shale
700 - 1100	Sand and shale
1100 - 1320	Red bed and shale
1320 - 1535	Sand
1535 - 1795	Shale and red bed
1795 - 1835	Anhydrite
1835 - 1975	Shale, shells, red bed
1975 - 2365	Shale, shells, salt
2365 - 2905	Shale and lime
2905 - 3160	Shale and lime
3160 - 3520	Lime and shale
3520 - 3640	Lime
3640 - 3690	Shale and lime
3690 - 3815	Lime
3815 - 3904	Lime
3904 - 3960	Shale, red bed, lime
3960 - 4020	Lime and shale
4020 - 4050	Lime, shale, chert
4050 - 4096	Cong.
4096 - 4122	Arbuckle
4122	Rotary Total Depth

Topeka	3409
Heebner	3623
Toronto	3642
Lansing	3659
Base K. C.	3904
Conglomerate	4064
Arbuckle	4092

I hereby certify that the above is a true and correct log, to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By: *Carl Todd*

PLUGGING
 FILE SEC 15 T 12 R 22w
 BOOK PAGE 22 LINE 2

12-14-1955