

15-195-00186-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Trego County, Sec. 15 Twp. 12 Rge. 22 NE/4 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE SW

Lease Owner C-G Drilling Co.

Lease Name Olson Well No. 1

Office Address 206 Union National Bank Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-10 1951

Application for plugging filed 10-7-51 1951

Application for plugging approved 10-7-51 1951

Plugging commenced 10-8-51 1951

Plugging completed 10-10-51 1951

Reason for abandonment of well or producing formation too low structurally

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, P. O. Box 326, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	212.16'	
				5 1/2"	4122.91'	3347.91'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with 20' of Chat in bottom, filled 10' in pipe, 4 sacks of cement on top of chat. Filled hole to 210' with mud set rock bridge, 15 sacks cement on rock bridge, filled with mud to 35' rock bridge set and 10 sacks cement to top of surface.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 18 1951  
CONSERVATION DIVISION  
10-18-1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C-G Drilling Co. I  
Address 206 Union National Bank Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Vicky Fritz (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vicky Fritz


206 Union National Bank Bldg. (Address)

SUBSCRIBER AND SWORN to before me this 15th day of Oct., 1951

My commission expires August 11, 1954 Notary Public. Almeda Rowe

22-7377-8 4-49-10M

PLUGGING  
FILE SEC 15 T 12 R  
BOOK PAGE 146 LINE 37



CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. FARM Olson #1  
 LOCATION SE SE SW Sec. 15-12-22W  
 POOL NAME W. C. COUNTY Trego STATE Kansas  
 COMMENCEMENT DATE 8-27-51 COMPLETION DATE 10-10-51

LOG OF WELL

Elevation 2380 R. B.  
 All Measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	170			
170	210			
210	1090	Shale-Sand		
1090	1135	Sand		
1135	1155	Shale		
1155	1300	Shale-Sand		
1300	1525	Sand	1500-00	
1525	1700	Red Bed		
1700	1808	Shale		
1808	1850	Anhydrite		
1850	1950	Shale		
1950	2175	Shale	2000-00	
2175	2330	Shale		
2330	2490	Shale-Lime		
2490	2630	Shale-Lime	2500-00	
2630	2750	Lime-Shale		
2750	2840	Lime-Shale		
2840	2940	Shale-Lime		
2940	3020	Lime-Shale	3000-00	
3020	3065	Shale-Lime		
3065	3135	Lime-Shale		
3135	3220	Lime-Shale		
3220	3265	Lime-Shale		
3265	3365	Lime-Shale		
3365	3460	Lime-Shale		
3460	3525	Lime	3500-00	
3525	3565	Lime-shale		
3565	3620	Lime		
3620	3685	Lime-Shale		
3685	3720	Lime-Shale		
3720	3770	Lime		
3770	3810	Lime		
3810	3850	Lime		
3850	3910	Lime		
3910	3955	Lime-Shale		
3955	4005	Lime-Shale		
4005	4034	Lime-Shale-Chert		
4034	4080	Shale-Lime		
4080	4103	Lime		

STATE OF KANSAS  
 10-18-1951  
 OCT 18 1951  
 COUNTY OF TREGO

CASING LEFT IN HOLE AFTER COMPLETION

Set (212.16' 10 jts) of 8 5/8" OD Casing  
 776' of 5 1/2" Casing

STATE OF KANSAS, COUNTY OF SEDGWICK) SS

**PLUGGING**  
 FILE SEC 15-12-22W  
 BOOK PAGE 166 LINE 37

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

Subscribed and sworn to before me this 15th day of October, 1951  
 My Commission Expires: 8-11-51

C-G DRILLING CO.

By Wiley Fritz

Abner Lowe  
 Notary Public

