

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM County. Sec. 15 Twp. 10S Rge. (E) 24 (W)

Location as "NE/CNWxSWx" or footage from lines C SW SE  
Lease Owner GLEN N. RUPE  
Lease Name SPROUL Well No. 1  
Office Address 222 BROWN BLDG., WICHITA, KANSAS 67202  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JAN. 7, 1967  
Application for plugging filed (PHONE 1/7/67) JAN. 10, 1967  
Application for plugging approved JAN. 7, 1967  
Plugging commenced JAN. 7, 1967  
Plugging completed JAN. 7, 1967  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS  
Producing formation Depth to top Bottom Total Depth of Well 4016 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	215	8-5/8"	215'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 600 FEET. SET FIRST PLUG AT 600 FEET WITH 1/2 SACK HULLS AND 20 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 210 FEET. SET SECOND PLUG AT 210 FEET WITH 1/2 SACK HULLS AND 23 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET THIRD PLUG AT 40 FEET WITH 10 SACKS CEMENT. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB COMPLETE @ 2:30 AM.

RECORDED  
STATE CORPORATION COMMISSION  
JAN 11 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.  
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
830 SUTTON PLACE, WICHITA, KANSAS 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 10TH day of JANUARY, 19 67

My commission expires FEBRUARY 1, 1968

[Signature]  
BARBARA J. LAYTON Notary Public.

15-065-30213-0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

SPROUL #1  
C SW SE SECTION 15-10S-24W  
GRAHAM COUNTY, KANSAS


COMMENCED: DECEMBER 29, 1966  
COMPLETED: JANUARY 7, 1967

STATE OF KANSAS  
JAN 10 1967  
CONSERVATION DIVISION

OPERATOR - GLEN N. RUPE

DEPTH		FORMATION	REMARKS
FROM	TO		
0	215	CLAY AND SHALE	RAN 6 JOINTS OF 8-5/8" CASING, SET @ 215' w/125 SACKS CEMENT.
215	465	SHALE	
465	1300	SHALE AND SHELLS	
1300	1390	SAND	
1390	1600	SHALE	
1600	1825	SAND	
1825	2085	SHALE AND RED BED	
2085	2115	ANHYDRITE	
2115	3685	SHALE AND LIME	
3685	4016	LIME	
4016	TD		DRY AND ABANDONED.


I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW SE SECTION 15-10S-24W, GRAHAM COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

  
E. E. HALL

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 10TH DAY OF JANUARY, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

  
BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.