

15-065-02166-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Graham County. Sec. 24 Twp. 10 Rge. (E)24 (W)  
Location as "NE/CNW%SW%" or footage from lines SE SE SE  
Lease Owner Musgrove Petroleum Corporation  
Lease Name McCOY Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed February 19, 19 56  
Application for plugging filed verbally - February 18, 19 56  
Application for plugging approved verbally - February 18, 19 56  
Plugging commenced February 19, 19 56  
Plugging completed February 19, 19 56  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3990 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.


Filled hole with heavy mud to 190'  
Set first plug at 190' with 15 sx cement  
Filled hole with heavy mud to 40'  
Set second plug at 40' with 10 sx cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of February, 1956  
My commission expires June 16, 1959.



Dean Jaye Hefler  
Notary Public.

FEB 25 1956  
02-25-56  
CONSERVATION DIVISION  
WICHITA, KANSAS

PLUGGING  
FILE SEC 24 T 10 R 24W  
BOOK PAGE 41 LINE 22

15-205-02166-0000

CONTRACTOR'S WELL LOG

COMPANY: MUSGROVE PETROLEUM CORPORATION  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: McCoy #1  
 LOCATION: SE SE SE, Section 24-10-24W  
 Graham County, Kansas  
 COMMENCED: February 8, 1956  
 COMPLETED: February 19, 1956

0	30	Surface soil
30	120	Sand, rocks, clay
120	195	Blue shale
195	1320	Shale & shells
1320	1421	shale
1421	1733	Red bed & sand
1733	2010	Shale & shells
2010	2300	Shale & lime
2300	2360	Lime
2360	2885	Shale & lime
2885	2935	Lime
2935	3735	Lime & shale
3735	3941	Lime
3941	3990	Lime & shale
	3990	Rotary T. D.

Set 8-5/8" surface pipe at 195' with 150 sacks cement, 2% calcium chloride.  
 Dry and Abandoned.

ELEVATION:	2405' K. B.	Toronto	3742'	(-1337)
TOPS: Topeka	3503' (-1098)	Lansing	3755'	(-1350)
Heebner	3718' (-1313)	Base K. C.	3984'	(-1579)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the McCoy #1, SE SE SE Section 24-10-24 West, Graham County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION  
 By Gordon L. Koelling  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of February, 1956.

Leah Joyce Wolfe  
 Notary Public

My commission expires June 16, 1959.



**PLUGGING**  
 FILE SEC 24 T 10 R 24W  
 BOOK PAGE 41 LINE 22

RECEIVED  
 STATE OF KANSAS DEPARTMENT OF CONSERVATION  
 FEB 25 1956  
 CONSERVATION DIVISION  
 Wichita, Kansas