


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Graham County. Sec. 25 Twp. 10S Rge. 24 (E) 24 (W)  
Location as "NE/CNW%SW%" or footage from lines NW SW NW  
Lease Owner Musgrove Petroleum Corporation  
Lease Name BILLINGS A Well No. 1  
Office Address 518 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed September 20, 19 55  
Application for plugging filed verbally - September 20, 19 55  
Application for plugging approved verbally - September 20, 19 55  
Plugging commenced September 20, 19 55  
Plugging completed September 20, 19 55  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4010 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 200'  
Set 1st plug at 200' w/155 sx cement.  
Filled hole w/heavy mud to 40'  
Set 2nd plug at 40' w/10 sx.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick  
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 55

My commission expires June 16, 1959  
Leah Faye Hefke Notary Public.

PLUGGING  
FILE SEC 22 T10 R24W  
BOOK PAGE 3 LINE 24

231755 09-28-55  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	BILLINGS A #1
LOCATION:	NW SW NW Section 25-10S-24W Graham County, Kansas
COMMENCED:	September 7, 1955
COMPLETED:	September 20, 1955

0	100	Surface soil & post rock
100	150	Sand & gyp
150	208	Lime streaks, gyp & blue shale
208	1550	Shale
1550	1790	Sand
1790	2070	Shale & lime
2070	2235	Red bed, shale & lime streaks
2235	2740	Lime & shale
2740	2775	Lime
2775	3809	Lime & shale
3809	4010	Lime
	4010	Rotary Total Depth

Set 8-5/8" surface casing at 208' w/150 sacks cement, 2% calcium chloride.

D & A

ELEVATION:	2415' K. B.	TOPS:	Topeka	3715' (-1300)
			Heebner	3732' (-1317)
			Toronto	3754' (-1339)
			Lansing	3770' (-1355)

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK    )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the BILLINGS A #1, NW SW NW, Section 25-10S-24W, Graham County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling  
Gordon L. Koelling, Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 27th day of September, 1955.

Leah Faye Heike  
Leah Faye Heike, Notary Public

My commission expires June 16, 1959.



**PLUGGING**  
WELL SEC 25 T-10-R 24W  
BOOK PAGE 3 LINE 24