


15-005-20164-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County, Sec. 29 Twp. 10 Rge. 24 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner Don E. Pratt Oil Operations
Lease Name C. Hanna Well No. 1
Office Address Box 390, Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-11 1968
Application for plugging filed 9-11 1968
Application for plugging approved 9-11 1968
Plugging commenced 9-11 1968
Plugging completed 9-11 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	153'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug was set @ 1100' with 100 sacks cement
2nd. plug was set @ 185' with 20 sacks cement
3rd. plug was set @ 40' with 10 sacks cement
Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1968
My commission expires September 19, 1970



Joseph A. Hess
JOSEPH A. HESS
Notary Public.

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company	Don E. Pratt Oil Operations Box 390 Hays, Kansas 67601	Sec. 29	Twp. 10	Req. 24
Farm	C. Hanna No. 1 3930	Location	NE NW NE	
Total Depth	3390' 2.1 KCC	County	Graham	
Comm.	8-21-68 Comp. 9-11-68	Elevation:	2409'	K. B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671		2406'	D. F.
			2404'	G. R.
		Production:	D & A	
	Casing Record 153' - 8 5/8"	Cement Record	135 sacks cement	

Figures Indicate Bottom of Formations

0'	40'	Surface Soil & Sand & Rock
40'	120'	Yellow Clay & Rock
120'	153'	Blue Shale
153'	935'	Shale & Shells
935'	1025'	Sand
1025'	1110'	Shale & Sand Streaks
1110'	1570'	Sand & Shale
1570'	1758'	Sand
1758'	2021'	Shale & Redbed
2021'	2058'	Anhy.
2058'	2280'	Shale
2280'	2546'	Shale & Shells
2546'	2875'	Shale & Lime
2875'	3085'	Lime
3085'	3380'	Shale & Lime
3380'	3558'	Lime
3558'	3664'	Lime
3664'	3730'	Lime & Shale
3730'	3930'	Lime
3930'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 17 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your C. Hanna #1.

Leo F. Dreiling

 LEO F. DREILING

Subscribed and sworn to before me this 16th day of September 1968.



Joseph A. Hess

 JOSEPH A. HESS NOTARY PUBLIC