

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-20,928-00-00

LEASE NAME Pearson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3

330 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Ritchie Exploraiton, Inc.

SEC. 11 TWP. 12 RGE. 22 (E) or (W)

ADDRESS P.O. Box 783188, Wichita, KS 67278-3188

COUNTY Trego

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Date Well Completed 4/2/82

Character of Well oil

Plugging Commenced 11/15/99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11/15/99

The plugging proposal was approved on November 18, 1999 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? filed with CP-1

Producing Formation Toronto/LKC Depth to Top 3643 Bottom 3906 T.D. 3737

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	oil & Brine	3643	3658	8 5/8"	207'	-0-
LKC	oil & brine	3650	3906	4 1/2"	4107'	-0-

RECEIVED
KANSAS CORP COM
DEC 16 11:12
12-16-1999

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Perforated 4 1/2" casign at 1850' (anhydrite) Ran 2 3/8" tubing to 3644'. Pumped 75 sacks 60/40 pozmix with 10% gel & 200# hulls. Pulled tubing up to 1805' Pumped 75 sacks 60/40 pozmix with 10% gel & 200# hulls. Pulled out of hole. Loaded and squeezed 4 1/2" casing with 30 sacks 60/40 pozmix with 10% (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Express Well Service, Inc. License No. 6426

Address 1110 Hwy 40, P.O. Box 426, Victoria, KS 67671-0426

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

John C. Neisenberg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.
(Signature) [Signature]

(Address) P.O. Box 783188, Wic., KS 67278

ANDREA PEREZ
Notary Public - State of Kansas
My Appt. Expires 01-26-2002

Subscribed AND SWORN TO before me this 13th day of December, 1999

[Signature]
Notary Public
Andrea Perez

My Commission Expires: 01-26-2002

gel. Max psi = 800#. Shut in at 800#. pumped 50 sacks 60/40 pozmix
with 10% gel and 200# hulls sown 8 5/8" casing. Max PSI = 500#
Shut in at 200#. Plugging complete at 5:15 pm. Witnessed and approved
by Jay Pfeifer with Kansas Corporation Commission, Hays, Kansas.