

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
STATE CORPORATION COMMISSION Rev. 12-15-80
9-20-1982
SEP 20 1982

WELL PLUGGING RECORD

CONSERVATION DIVISION
Wichita, Kansas

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 28 TWP. 10S RGE. 23 XE/W
Location as in quarters or footage from lines:
NW/4 of NW/4 of SE/4

		28	

Lease Owner Sun Exploration & Production Company
Lease Name Diebolt LKC Unit Well No. 15-1
Office Address P.O. Box 35567, Tulsa, Oklahoma 74135
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed December 9, 1954
Application for plugging filed July 28, 1982
Plugging commenced September 8, 1982
Plugging completed September 8, 1982
Reason for abandonment of well or producing formation
No oil production

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation LKC Depth to top 3781 bottom 3840 T.D. 4143'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		Surface	411'	9-5/8"	411'	None
LKC	Oil	Surface	3935	5-1/2"	3935'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from 3215 feet
to 2629 feet for each plug set.

Tag PBTB 3215'. Spot 50 Sx. 50-50 Pozmix w/2% gel & 3% CaCl from 3215' to 2629'.
Spot 25 Sx. gel 2629' to 1400'. Spot 180 Sx. 50-50 Pozmix w/2% gel & 3% CaCl from
1400' to surface. Squeeze surface w/10 Sx. 50-50 Pozmix w/2% gel & 3% CaCl to 50#.
Weld steel plate on surface casing.

NOTE: Unable to recover 636' tbq. stuck in hole - top of the tbq. is 3215'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Superior Well Service

STATE OF Oklahoma COUNTY OF Tulsa, ss.

D. J. Van Orden (~~employee of owner~~) (~~owner~~) (~~operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) D. J. Van Orden
P.O. Box 35567, Tulsa, OK. 74135
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of September, 19 82

Maie Whip
Notary Public.

My Commission expires: October 2, 1983

