


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines Graham County, Sec. 18 Twp 10 Rge. 24 (E)W (W)  
NE SE SE  
Lease Owner Don E. Pratt Oil Operations  
Lease Name Hobbs Well No. 2  
Office Address Box 390, Hays, Kansas 67601  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4-29 1968  
Application for plugging filed 4-29 1968  
Application for plugging approved 4-29 1968  
Plugging commenced 4-29 1968  
Plugging completed 4-29 1968  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	176'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st. plug was set at 1175' with 100 sacks cement  
2nd. plug was set at 180' with 20 sacks cement  
3rd. plug was set at 40' with solid bridge and 10 sacks cement  
Cementing to bottom of cellar.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS COUNTY OF ELLIS, ss. \_\_\_\_\_  
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671  
(Address)



Subscribed and sworn to before me this 30th day of April, 1968  
Joseph A. Hess  
JOSEPH A. HESS Notary Public.

**L. J. DREILING and SONS, Inc.**  
**VICTORIA, KANSAS**

**WELL LOG**

Company	Don E. Pratt Oil Operations Box 390 Hays, Kansas 67601	Sec. 18	Twp. 10	Rng. 24
Farm	Hobbs No. 2	Location	NE SE SE	
Total Depth	3970'	County	Graham	
Comm.	4-21-68 Comp. 4-29-68	Elevation:	2445'	K.B.
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		2442'	D. F.
	Casing Record	Cement Record	2440'	G. R.
	176' - 8 5/8"	135 sacks cement	Production: D & A	

Figures Indicate Bottom of Formations

0'	176'	Surface Soil
176'	200'	Shale
200'	1430'	Shale
1430'	1465'	Shale
1465'	1624'	Shale with Sand Streaks
1624'	1820'	Sand
1820'	1980'	Shale
1980'	2066'	Shale
2066'	2104'	Anhy.
2104'	2451'	Shale & Lime
2451'	2625'	Shale & Lime
2625'	2870'	Shale & Lime
2870'	3075'	Shale & Lime
3075'	3260'	Shale & Lime
3260'	3415'	Shale & Lime
3415'	3590'	Shale & Lime
3590'	3640'	Shale & Lime
3640'	3735'	Lime
3735'	3767'	Lime
3767'	3815'	Lime
3815'	3873'	Shale & Lime
3873'	3880'	Lime
3880'	3900'	Lime
3900'	3925'	Lime
3925'	3945'	Lime
3945'	3970'	Lime
3970'	T.D.	

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 1 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS)  
 )ss  
 COUNTY OF ELLIS)

I, Leo F. Dreiling of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Hobbs #2.

*Leo F. Dreiling*  
 LEO F. DREILING



*Joseph A. Hess*  
 JOSEPH A. HESS NOTARY PUBLIC

Subscribed and sworn to before me this 30th day of April 1968.

My commission expires: September 19, 1970