

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-065-22490-00-00

API NUMBER 15-065-22,490

LEASE NAME Ruder "A"

WELL NUMBER 2

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 18 TWP. 10SRGE. 24 (EXXX W)

COUNTY Graham

Date Well Completed 10-03-88

Plugging Commenced 10-03-88

Plugging Completed 10-04-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 780407, Wichita, KS 67278

PHONE# (316) 685-1441 OPERATORS LICENSE NO. 5131

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-04-88 (date)

by State Plugger, Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3960'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	From	To	Size	Put in	Pulled out
			8 5/8"	271 15'	None

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1988  
CONSOLIDATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Circulate heavy mud. 1st plug from 2070' to 1970' w/25 sx. 2nd plug from 1235' to 835' w/100 sx and 1 sx Flocel. 3rd plug from 320' to 160' w/40 sx. 4th plug from 40' to surface w/10 sx. Rathole 15 sx. All cement 60/40 posmix, 6% gel, 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 88

Janice M. Walker  
Notary Public

Commission Expires: 10/24/90

