

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market - Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-20007-~~0000~~ ⁰⁰⁻⁰¹

API NUMBER 1/31/67
 LEASE NAME D. Rush 'A'
 WELL NUMBER 2
2970 Ft. from S Section Line
3630 Ft. from E Section Line
 SEC. 20 TWP. 10S RGE. 24W (E) or (W)
 COUNTY Graham
 Date Well Completed 2/18/67
 Plugging Commenced 4/11/2000
 Plugging Completed 4/11/2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.
 ADDRESS P. O. Box 70 Hays, KS 67601
 PHONE# (785) 625-0020 OPERATORS LICENSE NO. 9067
 Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/11/2000 (date)
 by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? ? If not, Is well log attached? yes
 Producing Formation Lansing-Kansas City Depth to Top 3745 Bottom 3979 T.D. 3993 (RTD)

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8.5/8"	186'	none
				4 1/2"	3992	none

MAY 4 2000
5-4-2000
CONSERVATION DIVISION
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
CIBP set @ 3650. Pump 50 sx 60/40 poz w/10% gel and 100# hulls down 4 1/2" - 8 5/8" annulus, pressure up to 200#, shut in. Pump 180 sx 60/40 poz w/10% gel and 400# hulls down 4 1/2" casing, pressure up to 400#, shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. NA

Address P. O. Box 31 Russell, KS 67665


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601



READ AND SWORN TO before me this 3rd day of May, 2000

Vickie Cole
 Notary Public

My Commission Expires: 10-18-2000