

15-065-30221-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-06530221

LEASE NAME G. Rush 'C'

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 20 TWP. 10 RGE. 24 (W) or (E)

COUNTY Graham

Date Well Completed 1/3/79

Plugging Commenced 8/31/98

Plugging Completed 8/31/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE# (913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/31/98 (date)

by Rick Williams (KCC District Agent's Name).

Is ACO-1 filed? ? If not, Is well log attached? Yes

Producing Formation Lansing-Kansas City Depth to Top 3710 Bottom 3941 T.D. 3925?

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Anhydrite		2014	2054	8 5/8	180'	none
				4 1/2	3959	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump through tubing at 3205', 75 sx cement (60-40 poz w/1090 gel) with 100# of hulls. Pump through tubing at 2077', 75 sx cement with 200# hulls. Pump through tubing at 1142', 35 sx cement with 100# hulls, hole full. Pump down 4 1/2" casing, 25 sx cement up to 500#, shut in @ 400#. Pump 75 sx cement and 100# hulls down 4 1/2" / 8 5/8" annulus up to 400#, shut in @ 300#.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) POB 70 Hays KS 67601

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 98



My Commission Expires: 10-18-2000 Notary Public

RECEIVED
KANSAS CORP COM
1998 SEP 14 11:41 AM
9-14-1998