

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER UNKNOWN

LEASE NAME G. RUSH "A"

WELL NUMBER 1

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 20 TWP. 10S RGE. 24W (E) or (W)

COUNTY GRAHAM

Date Well Completed 2/ /67

Plugging Commenced 2/26/90

Plugging Completed 2/28/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CRUMP PETROLEUM CORP.

ADDRESS P.O. BOX 50820, MIDLAND, TEXAS 79701

PHONE# (915) 687-2008 OPERATORS LICENSE NO. 03135

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/27/90 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filled? NO If not, Is well log attached? YES

Producing Formation LANSING-K.C. Depth to Top 3728 Bottom 3966 T.D. 3970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LANSING-K.C.	Depleted oil	3730	916	8-5/8"	162'	None
				4 1/2"	3929	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Attempted to pull tbq. Tbg was badly corroded and parted at 8', 22' & 69'. Ran free-point and backed off at 1350' [could not get past this point due to damaged tbq. Ran tbq. to 1353 & pumped 150 sxs 65-35 pozmix + 8% gel + 300# hulls. Sqzd with additional 75 sxs + 150# hulls. Sqzd. annulus w/ 175 sxs + 50# hulls S-I. Press 200 psi. BACK of this form.)

Name of Plugging Contractor MURFIN DRILLING CO. License No. 6033

Address P.O. Box 130, Hill City, Kansas 67642


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CRUMP PETROLEUM CORP.

STATE OF TEXAS COUNTY OF TARRANT, ss.

ROBERT D. BOCELL, AGENT

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert D. Boccell, Agent
(Address) 2115 Melissa St., Arlington, TX 76010



SUBSCRIBED AND SWORN TO before me this 6 day of MARCH, 1990

Maryann Starrett
Notary Public

My Commission Expires: 2/27/92