

15-051-30685-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 16 Twp. 11S Rge. (E) 18 (W)

Location as "NE/CNWxSWx" or footage from lines SE SE SE

Lease Owner Sohio Petroleum Company

Lease Name Madden Well No. 1

Office Address Box 673, Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-26 19 50

Application for plugging filed 7-8 19 66

Application for plugging approved 7-12 19 66

Plugging commenced 9-1 19 66


Plugging completed 9-6 19 66

Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production August 19 66

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3492 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1232'	
				5 1/2"	3481'	2529'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 5 sacks of cement on bottom.

Plug at 3260'.

Set bridge plug at 450'; dumped one sack cement on top;

dumped 6 yards ready mix cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
D. W. Smith (employee of owner) or XXXXXXXXXXXX of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]


(Address) _____

SUBSCRIBED AND SWORN to before me this 7th day of September, 19 66

Deanne Becker

Notary Public.

My commission expires November 18, 1967



Langfren Exp. Co.
 WADEN NO. 1

SE 1/4 SE 1/4 Sec. 16-11S-18W, Ellis County, Kansas

Rigging up Rotary Tools 3-6-50
 Tearing down Rotary Tools 3-21-50
 Rigging up Cable Tools 3-23-50
 Tearing down Cable Tools 3-26-50

Ran 55 lbs. 8 5/8" surface pipe. Set at 1232' and cemented with 500 sx cement.
 Ran 107 lbs. 5 1/2" casing. Set at 3481 1/2' and cemented with 150 sx cement.

FORMATION	ROD	FO
Shale	0	40
Shale and sand	40	480
Sand	480	550
Shale and shells	550	710
Sand	710	835
Sand and redbed	835	1195
Redbed	1195	1222
Anhydrite	1222	1230
Anhydrite and redbed	1230	1445
Redbed and shale	1445	1520
Salt and redbed	1520	1700
Shale and shells	1700	1925
Shale and lime	1925	2940
Lime	2940	3020
Lime and shale	3020	3050
Lime	3050	3095
Lime and shale	3095	3255
Lime	3255	3418
Lime, shale, chert	3418	3470
Lime	3470	3486
Arbuckle	3486	3492 Total Depth

I, Don S. Packer, hereby certify that the above log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 1st day of May, 1950.

 Notary Public

Commission expires: March 22, 1952.

Contractor: Harbar Drilling Company

MAY 3 1950
 MATHE OIL CORP