

15-065-00539-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

GRAHAM County, Sec. 4 Twp. 10 Rge. (E) 25(W)

Location as "NE/CNWxSWx" or footage from lines SW SE SW

Lease Owner EMPIRE DRILLING COMPANY

Lease Name PFEIFER B Well No. 1

Office Address 650 FOURTH NATIONAL BANK BUILDING

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed MARCH 6, 1958 19

Application for plugging filed MARCH 6, 1958 19

Application for plugging approved MARCH 6, 1958 19

Plugging commenced MARCH 6, 1958 19

Plugging completed MARCH 6, 1958 19

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. D. FABRICIUS

Producing formation Depth to top Bottom Total Depth of Well 4085 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	SURFACE	0	151	8 5/8	151	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

BOTTOM PLUG @ 600' WITH 20 SACKS CEMENT. PLUG AT 150' WITH 15 SACKS CEMENT  
PLUG AT 40' WITH 10 SACKS CEMENT TO SURFACE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY

Address 650 FOURTH NATIONAL BANK BUILDING WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

I, THEODORE GORE, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore

650 FOURTH NATIONAL BANK BUILDING (Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of MARCH, 19 58

My commission expires JULY 2, 1958

Hazel Peterson Notary Public.

3-15-1958  
MAR 15 1958

PLUGGING  
FILE SEC 4 T. 10 R. 25  
BOOK PAGE 88 LINE 24

CONSERVATION DIVISION  
Wichita, Kansas

L O G

COMPANY: EMPIRE DRILLING COMPANY WICHITA, KANSAS  
 CONTRACTOR: EMPIRE DRILLING COMPANY WICHITA, KANSAS  
 FARM: PFEIFER "B" # 1  
 LOCATION: SW SE SW SECTION 4-10-25W GRAHAM COUNTY, KANSAS  
 COMMENCED: FEBRUARY 25, 1958 ELEVATION: 2555 KB  
 COMPLETED: MARCH 6, 1958 POTENTIAL:

---

0	TO	167	SURFACE
167	TO	1370	CLAY, SHALE AND SAND
1370	TO	1675	SHELLS AND SHALE
1675	TO	2187	SAND AND SHALE
2187	TO	2225	ANHYDRITE
2225	TO	2775	SHALE AND SHELLS
2775	TO	3010	SHALE AND LIME
3010	TO	3810	LIME AND SHALE
3810	TO	3870	LIME
3870	TO	3900	LIME AND SHALE
3900	TO	4085	LIME
		4085	RTD


SET: 8 5/8" 151' WITH 115 SACKS CEMENT

TOPS: ANHYDRITE 2187  
 HEEBNER 3806  
 TORONTO 3830  
 LANSING KANSAS CITY 3847  
 BASE KANSAS CITY 4078

---

 C E R T I F I C A T I O N

I, THEODORE GORE, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE PFEIFER "B" NUMBER 1SW SE SW SECTION 4-10-25, GRAHAM COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

  
 THEODORE GORE

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 14TH DAY OF MARCH, 1958

  
 HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 2, 1958

3-15-1958

