

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-21108-00-00

LEASE NAME Rome

WELL NUMBER 1

2970 Ft. from S Section Line

1660 Ft. from E Section Line

SEC. 4 TWP. 10S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 5-79

Plugging Commenced 5-23-03

Plugging Completed 5-23-03

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS PO B 723 Hays, KS 67601

PHONES (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation AC Depth to Top \_\_\_\_\_ Bottom T.O. 4310

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>Surface</u>	<u>0</u>	<u>337</u>	<u>8 1/8</u>		
	<u>Prod.</u>	<u>0</u>	<u>405</u>	<u>4 1/2</u>		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to \_\_\_\_\_ feet each set.

Move in Rig. Rig up Perf Tech. Perf @ 2200', 1320, 380. Run tbg to 3773' Mix 100 sx cement w/400# hulls. Pull tbg to 1500' Mix 60 sx w/200# hulls. Circ. cement to surface, pull rest of tbg, hook up to CSG, Mix 35 sx. Press. to 900#, ST @ 500# hook up to 8 3/8 Pump 5 sx fill up surface to top. KCC rep Roger Moses witness.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address PO B 723 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Curt Gabel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Curt Gabel

(Address) PO B 723 Hays, KS

SUBSCRIBED AND SWORN TO before me this 10<sup>th</sup> day of June, 2003

Marion Sue Vance  
Notary Public

My Commission Expires: 4-30-06



KCC Form 9-1 Revised 05-88

JUN 13 2003

HAYS, KS