

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Victor Justus of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Justus guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: Mabelle Well No. 1

Location: NE-SW-NE Sec. 25 Twp. 10 Rge. (E)(W) 2h

County: Graham Total Depth 3955' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Justus was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
 Conservation Division Agent