

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
2-20-1973  
FEB 20 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Herman Fellhoelter of Kimbark Operating Company has this date requested permission to plug the following described well:

Mr. Fellhoelter guarantees payment of the plugging fee.

Operator's full Name: Kimbark Operating Company,

Complete Address: 1776 Lincoln, Denver, Colorado.

Lease Name: Bernard Well No. 3

Location: CNE-NW Sec. 2 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4013' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Fellhoelter was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.  
4005'--4 1/2" Production casing cemented on bottom with 50 Sx. common cement and 600 gallons Latex, Top of cement @ 2800'. 2" Tubing Stub @ 3050' sanded off. 4 1/2" has been squeezed @ 1609' with 700Sx. cement.

Try to pump in 4 1/2" casing, if possible without excessive pressure squeeze 4 1/2" with enough cement to fill to surface. Try to pump in annulus, if possible squeeze with enough cement to reach at least 1100'.

Very truly yours,

M. L. Nichols  
Conservation Division Agent