

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 2-15-1967
 FEB 15 1967

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Csg. Pulling Co. has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.
 Texaco, Inc Authority dated 12/12/'66
 Operator's full Name: Knight Casing Pulling Company,

Complete Address: Box # 405, Chase, Kansas.

Lease Name: V. Rome Well No. 1

Location: CSE-SW Sec. 2 Twp. 10 Rge. (E)(W) 25

County Graham Total Depth 3978 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

200'--8 5/8" Surface casing cement circulated.
3977' 4 1/2" Production casing cemented with 125 Sx. No indication of any plug back or perforations.

Sand well to 3965' and set 3 Sx. cement with dump bailer.

Pull 4 1/2" casing, set rock bridge @ 225' and fill hole with

Redi-mix cement.

Very truly yours,

Conservation Division Agent