



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-195-20171-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 8 1971

CONSERVATION DIVISION  
Wichita, Kansas

01-08-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lyle Hicks of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Utica Southern Explorations Incorporated,

Complete Address: 808 Palace Building, Tulsa, Oklahoma.

Lease Name: Olson Well No. 1

Location: SE-SW-SW Sec. 15 Twp. 12 Rge. (E)(W) 22

County: Trego Total Depth 4095' Oil Well

Gas Well  Input Well  SWD-Well  D. & A. X Lost-Hole

Mr. Hicks was instructed to plug the well as follows:

228'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 625'.

Circulate hole with heavy mud. Pull DP to 850' and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent