

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Dunham of Aspen Drilling Company has this date requested permission to plug the following described well:

Mr. Dunham guarantees payment of the plugging fee.

Operator's full Name: Aspen Drilling Company,

Complete Address: Box #783, Great Bend, Kansas.

Lease Name: Pfeifer Well No. 1

Location: NE-SE-SW Sec. 5 Twp. 10 Rge. (E)(W) 25

County Graham Total Depth 4100 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dunham was instructed to plug the well as follows:

209'--8 5/8" Surface pipe, cement circulated with 140 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

"	"	210' with $\frac{1}{4}$ sk. hulls & 20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent