

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Kimbark Operating Company,

Complete Address: P. O. Box #86, Plainville, Kansas.

Lease Name: Vance Well No. 1

Location: NW-SW-SE Sec. 5 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4130 Oil Well X

Gas Well      Input Well    SWD Well    D & A    Lost Hole   

Mr. Unruh was instructed to plug the well as follows:

202'--8 5/8" Surface casing, cement circulated with 160 Sx.  
4121'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations from 3903' to 3907'.

Sand well back to 3850' and set 8 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent