



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sam Wagner of Red Tiger Drilling Company has this

date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 KSB&T Building, Wichita, Kansas.

Lease Name: McGuire Well No. C-1

Location: SW-NW-SW Sec. 8 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4010' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Wagner was instructed to plug the well as follows:

280'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 725'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 285' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

Conservation Division Agent