

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Delta Western Company,

Complete Address: c/o Jim Morris, 211 North Broadway, Wichita, Kansas.

Lease Name: Brungardt Well No. A-1

Location: SW-NE-NE Sec. 8 Twp. 10 Rge. (E)(W) 25

County: Graham Total Depth 4070' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

248'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent