

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
March 2009  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32864  
Name: XTO Energy, Inc.  
Address 1: 210 Park Ave. Suite 2350  
Address 2: \_\_\_\_\_  
City: Oklahoma City State: OK Zip: 73102 + \_\_\_\_\_  
Contact Person: Karen Byers  
Phone: (405) 319-3212

API No. 15 - 081-21768-0001  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
SW. SW. NE. NE Sec. 6 Twp. 27 S. R. 31  East  West  
1248 Feet from  North /  South Line of Section.  
1252 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Haskell  
Lease Name: Mathes B Well #: 11-6

*Per GPS  
3/4/10  
KJ  
3/15/10*

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: D30178.0  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8" Set at: 555' Cemented with: 280 Sacks  
Production Casing Size: 5 1/2" Set at: 3153' Cemented with: 525 Sacks

RECEIVED  
KANSAS CORPORATION COMMISSION

List (ALL) Perforations and Bridge Plug Sets:  
Perfs - 2646' - 2661' w/ 2 spf (31 holes)

MAR 05 2010

Elevation: 2838' ( G.L. /  K.B.) T.D.: 3160' PBTD: 3122' Anhydrite Depth: 1850' CONSERVATION DIVISION  
(Stone Corral Rd @ 1/2 mi. N. of JTA, KS)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

There is a RBP @ 2787' w/ 2 bags of sand on top. While attempting to squeeze off the Krider formation, cement migrated up through the Herington and up the casing to 1929'. The tubing was cut off @ 1929'. We plan to fill the casing with cement in 2 stages from 1929'-975' and 975'-surface.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: David Littell & Mark Gosch

Address: 805 S. Hwy 25 City: Lakin State: KS Zip: 67860 + 0383

Phone: (620) 272-1780 or 272-1996

Plugging Contractor License #: \_\_\_\_\_ Name: Unknown at this time

Address 1: \_\_\_\_\_ Address 2: \_\_\_\_\_

City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_ + \_\_\_\_\_

Phone: (\_\_\_\_) \_\_\_\_\_

Proposed Date of Plugging (if known): Unknown at this time

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/3/10 Authorized Operator / Agent: Karen Byers (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Ker  
m*



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

XTO ENERGY INC.  
210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102-5683

March 15, 2010

Re: MATHES B #11-6  
API 15-081-21768-00-01  
6-27S-31W, 4094 FSL 1280 FEL  
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after September 11, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888