

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY GRAHAM SEC. 9 TWP. 10s RGE. 25w E/W
Location as in quarters or footage from lines:
NW-SW-NE

		●	

Locate Well
correctly on above
Section Platt.

Lease Owner TENNECO OIL COMPANY
Lease Name ELRICK Well No. 10-1
Office Address 7301 NW EXPRESSWAY, P.O. BOX 25420, OKLAHOMA CITY, OK 73125
Character of Well (Completed as Oil, Gas or Dry Hole): OIL
Date Well Completed 1-25-58
Application for plugging filed 11-26-86
Plugging commenced 1-19-87
Plugging completed 1-22-87
Reason for abandonment of well or producing formation NON-COMMERCIAL

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GIL BALTHAZOR
Producing formation LKC Depth to top 3922 bottom 3972 T.D. 4010

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
LKC	oil & water	3922	3972	5 1/2	4009	NONE
				8 5/8	167	NONE
FLUID LEVEL	450'					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Run gauge ring to 2023'. Got large chunks of shale back. Casing collapsed or parted @ 2023'. Perforated 2 holes @ 2020', 2 holes @ 1275'. Pump 150 sks 60/40 poz-mix, 50 sks 60/40 poz-mix with 3 sks hulls, 50 sks 60/40 poz-mix Max pressure: 1600#, S.I.P.: 1000#. Could not pump into 8 5/8 @ 500#.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor PRODUCTION DRILLING, INC.

STATE OF KANSAS COUNTY OF ELLIS, ss.
LARRY L. PATTERSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. BOX 680 HAYS, KS 67601
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of Feb, 19 87

My Commission expires: 30 July 1987



Janet Klaus
Notary Public
STATE CORPORATION COMMISSION

FEB 5 1987
CONSERVATION DIVISION
Wichita, Kansas

L O G

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: RIEDEL B # 1
 LOCATION: NW SW NE SECTION 9-10-25, GRAHAM COUNTY, KANSAS
 COMMENCED: JANUARY 15, 1958 ELEVATION: 2508 KB
 COMPLETED: JANUARY 25, 1958 POTENTIAL: 215


0	TO	167	CLAY, SAND AND SHALE
167	TO	1010	SHALE
1010	TO	2133	SHALE AND SHELLS
2133	TO	2295	ANHYDRITE
2295	TO	2600	SHALE AND SHELLS
2600	TO	2922	SHALE AND LIME
2922	TO	3065	SHALE
3065	TO	3155	LIME AND SHALE
3155	TO	3215	SHALE AND LIME
3215	TO	3380	LIME AND SHALE
3380	TO	3550	SHALE AND LIME
3550	TO	3660	LIME AND SHALE
3660	TO	3745	SHALE AND LIME
3745	TO	4010	LIME
		4010	RTD

SET: 8 5/8" 167' WITH 115 SACKS CEMENT
 RAN: 5 1/2" 4009' WITH 50 SACKS PORTLAND CEMENT AND 25 SACKS LATEX
 D.V. TOOL @ 2169' SET WITH 100 BARRELS OF KEMPAQ

TOPS:	HEEBNER	3739
	TORONTO	3767
	LANSING KANSAS CITY	3784

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE RIEDEL B NUMBER 1, NW SW NE SECTION 9-10-25, GRAHAM COUNTY, KANSAS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.


 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 29TH DAY OF JANUARY, 1958


 HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 2, 1958