

15-065-03237-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY GRAHAM SEC. 9 TWP. 10s RGE. 25w E/W
Location as in quarters or footage from lines:
SE-NE-NE

Lease Owner TENNECO OIL COMPANY
 Lease Name ERLICK Well No. 10-3
 Office Address 7301 NW EXPRESSWAY, P.O. BOX 25420, OKLAHOMA CITY, OK. 73125
 Character of Well (Completed as Oil, Gas or Dry Hole): OIL
 Date Well Completed 9-15-58
 Application for plugging filed 11-26-86
 Plugging commenced 1-19-87
 Plugging completed 1-22-87
 Reason for abandonment of well or producing formation NON-COMMERCIAL

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GIL BALTHAZOR
Producing formation LKC Depth to top 3840 bottom 3959 T.D. 4265

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
LKC	oil & water	3840	3959	5 1/2	3960	NONE
				8 5/8	151	NONE
FLUID LEVEL	465'					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. C.I.B.P. @ 3690'. Spotted 5 sks cement on plug. Perforated 4 holes @ 1315'. Pump 50 sks 60/40 poz-mix, 3 sks hulls, 100 sks cement with 2 sks hulls blended. 50 sks 60/40 poz-mix. Max pressure: 600#. S.I.P.: 300# 50 sks 60/40 poz-mix down 8 5/8, Max pressure: 500#, S.I.P.: 300#. Topped with 1 yard Ready mix on 1-28-87

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PRODUCTION DRILLING, INC.


STATE OF KANSAS COUNTY OF ELLIS, ss.
LARRY L. PATTERSON (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P.O. BOX 680 HAYS, KS 67601
 (Address)

SUBSCRIBED AND SWORN TO before me this 3 day of Feb, 19 87

My Commission expires: 30 July 1987

[Signature]
 Notary Public.
 STATE CORPORATION COMMISSION



FEB 5 1987
 CONSERVATION DIVISION
 Wichita, Kansas

L O G


COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 FARM: RIEDEL "B" # 3
 LOCATION: SE NE NE SECTION 9-10-25W, GRAHAM COUNTY, KANSAS
 COMMENCED: SEPTEMBER 5, 1958 ELEVATION: 2535 KB
 COMPLETED: SEPTEMBER 15, 1958 POTENTIAL: 154

0	TO	162	SHALE AND SAND
162	TO	1385	SHALE, SHELLS AND SAND
1385	TO	2170	SHALE AND SHELLS
2170	TO	2205	ANHYDRITE
2205	TO	2940	SHALE AND SHELLS
2940	TO	3085	SHELE AND LIME
3085	TO	3215	LIME AND SHALE
3215	TO	3395	SHALE AND LIME
3395	TO	3785	LIME AND SHALE
3785	TO	4010	LIME
4010	TO	4140	LIME AND SHALE
4140	TO	4184	SHALE AND LIME
4184	TO	4265	SHALE
		4265	RTD

SET: 8 5/8" 151' WITH 100 SACKS CEMENT
 RAN: 5 1/2" 3966' WITH 75 SACKS CEMENT, 25 SACKS LATEX
 DV TOOL SET @ 2190' WITH 100 BARRELS OF K

TOPS: HEEBNER 3774
 TORONTO 3796
 LANSING KANSAS CITY 3811
 BASE OF KANSAS CITY 4047
 CHEROKEE GROUP 4244

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE RIEDEL "B" # 3, SE NE NE SECTION 9-10-25W, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.


 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 22ND DAY OF SEPTEMBER, 1958.


 LUCILLE HARR, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 21, 1958