

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-03234-0000

API NUMBER 15-N/A

LEASE NAME Elrick Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 9-4

4290
990 Ft. from S Section Line

3300
660 Ft. from E Section Line
RCL

LEASE OPERATOR Citation Oil & Gas Corp.

SEC. 9 TWP. 10 RGE. 25 ~~XXX~~ or (W)

ADDRESS 8223 Willow Place South Ste 250 Houston, Texas 77070 COUNTY Graham

PHONE# (281) 469-9664 OPERATORS LICENSE NO. 03553 Date Well Completed 6-29-58

Character of Well Oil Plugging Commenced 1-9-97

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 1-9-97

The plugging proposal was approved on 9-17-96 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filled? unknown If not, is well log attached? Already submitted

Producing Formation LKC Depth to Top 3974 Bottom 3980 T.D. 4044 4250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	3974	3980	8 5/8	148	0
				5 1/2	4044	1304

1-27-97
Ward
1-27-97

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU PU. RIH w/dump bailer. Dump'd 5 sxs cmt on top of CIBP @ 3725'. Perf'd @ 1304' w/1 shot. Csg free @ 1304'. Pump'd 20 sx 60/40 Poz w/10% gel & 300# hulls. Tailed w/80 sxs 60/40 Poz w/10% gel, displaced to 1200'. POOH w/70 jts 5 1/2" prod csg. Pmp'd 80 sx 60/40 Poz w/10% gel w/150# hulls displaced w/2 BW. POOH w/32 jts 5 1/2" prod. csg. Cmt'd to surf w/80 sx 60/40 Poz +10% gel. POOH w/2 jts 5 1/2" prod. csg. Top surf csg off w/cmt. RD MO Pmp'd 260 sx cmt. Carl Gudrow on location. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Haliburton Services License No. _____

Address 1102 East 8 Hays, KS 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Citation Oil & Gas Corp.

STATE OF Texas COUNTY OF Harris, ss.

Sharon Ward of Citation Oil & Gas Corp. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Sharon Ward

(Address) 8223 Willow Place South Ste 250 Houston, Texas 77070



SUBSCRIBED AND SWORN TO before me this 20th day of January, 19 97

Renee Harrell
Notary Public

My Commission Expires: 3-2-99