

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-22,097-00-00

LEASE NAME Sherfick So.

WELL NUMBER 24-22-66

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 24 TWP. 12 RGE. 22 (W)

COUNTY Trego

Date Well Completed 12-3-91

Plugging Commenced 12-3-91

Plugging Completed 12-3-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pioneer Oil and Gas

ADDRESS 6925 Union Park Center, Suite 145, Midvale, UT 84047

PHONE# (801) 566-3000 OPERATORS LICENSE NO. 30676

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-2-91 (date)

by Carl Goodrow - KCC, Hays (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation N/A Depth to Top _____ Bottom T.D. 4100

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Cedar Hills	water	surf	260	8 ⁵ / ₈ '	<u>1/2</u>	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Hole filled with 9.7# mud between plugs. Plugs set by displacement method through drill pipe. Plug #1: 25 Sacks at 1800', Plug #2: 100 sacks at 950', Plug #3: 40 sacks at 300', Plug #4: 10 sacks at 40'. 15 sack plug in rathole, 10 sack plug in mousehole. Total cement used-200 sacks 60/40 PozMix with 2% CaCl and 6% Gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. N/A

Address P.O. Box 31, Russell, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Anderson

STATE OF Utah COUNTY OF Salt Lake, ss.

Jason G. Blake

(Employee of Operator) or (Operator) of

above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct.

RECEIVED

KANSAS CORPORATION COMMISSION


(Signature) John O. Anderson

(Address) Midvale, UT (as above)

AND SWORN TO before me this 6th day of December, 19 91

John O. Anderson
Notary Public

Commission Expires: _____



DEC 12 1991

12-12-1991

CONSERVATION DIVISION
WICHITA, KS