

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-195-21,450-00-00

LEASE NAME STECKLINE

WELL NUMBER "B" #1

SPOT LOCATION NE NW NE

SEC. 24 TWP. 12S RGE. 22 (E) OR (W)

COUNTY TREGO

DATE WELL COMPLETED 2/28/84

PLUGGING COMMENCED 2/28/84

PLUGGING COMPLETED 2/28/84

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR JOHN JAY DARRAH, JR.

ADDRESS 405 CENTURY PLAZA BLDG. WICHITA, KS. 67202

PHONE # (316) 263-8218 OPERATORS LICENSE NO. 5088

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? PALCO

IS ACC-1 FILED? yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION none DEPTH TO TOP _____ BOTTOM T.D. 3950'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	surface	0	270	8 5/8"	261.82'	

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Plugged with 190 sx. 50/50 pozmix, 6% gel, 3% CACL, 2 sx. cell-o-flak, as follows:
1st plug @ 1720' w/ 20 sx. 2nd plug @ 900' w/ 100 sx. 3rd plug @ 260 w/ 40 sx. 10 sx and solid bridge @ 40' 10 sx. each in mousehole and rathole. PD @

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) 4:30 A.M. 2/28/84

NAME OF PLUGGING CONTRACTOR ALLIED CEMENTING CO. LICENSE No. _____
ADDRESS BOX 678 GREAT BEND, KS. 67530


STATE OF KANSAS COUNTY OF SEDGWICK SS.

JOHN JAY DARRAH, JR. (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) *John Jay Darrah, Jr.*
405 Century Plaza Bldg.
(ADDRESS) Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO BEFORE ME THIS 21st DAY OF March, 1984/

Patricia C. Byerlee
NOTARY PUBLIC
Patricia C. Byerlee



MY COMMISSION EXPIRES: December 11, 1985

RECEIVED
STATE CORPORATION COMMISSION
03-30-1984
MAR 30 1984
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83