


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Trego County, Sec. 25 Twp. 12 Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner United Drilling, Inc.
Lease Name Powers Well No. 1
Office Address Mohl Building, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 2, 1954 19 54
Application for plugging filed April 2, 1954 19 54
Application for plugging approved 19
Plugging commenced April 2, 1954 19 54
Plugging completed April 2, 1954 19 54
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. R. Petty
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 4043 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged from 4043 to 165 - Heavy drilling mud
165 to 120 - 1/2 sack hulls; 20 sacks cement
120 to 35 - Drilling mud
35 - 0 - 10 sacks cement and hulls

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor United Drilling, Inc.
Address Mohl Building, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Clyde G. Kissinger (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Clyde G. Kissinger*
Mohl Building, Russell, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 29th day of April, 19 54
Margaret Zuck
Notary Public.

My commission expires October 30, 1957

24-7368-S 3-53-20M RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 25 T 12 R 224
BOOK PAGE 25 LINE 1

APR 30 1954
04-30-1954
CONSERVATION DIVISION
Wichita, Kansas

15-195-01087-00-00

POWERS #1 WELL

Contractor: United Drilling, Inc.
Operator: United Drilling, Inc.
Commenced: March 20, 1954
Completed: April 2, 1954

LOCATION: SE NE SW
Section 25-12-22
Trego County, Kansas

Casing Record:

8 5/8" set at 170 feet.

- WELL LOG -

50	Soil and Sand
70	Shale
170	Shale
360	Salt and Sand
1500	Red Bed
1740	Anhydrite
1790	Red Bed and Shale
1910	Shale and Shells
2470	Lime and Shale
2745	Shale and Lime Streaks
2880	Lime and Shale
3190	Lime and Shale
3420	Lime
3670	Lime
3870	Lime and Shale
3950	Lime
3980	Lime and Shale
4043	Total Depth

STATE OF KANSAS }
COUNTY OF RUSSELL } SS:

I hereby certify that the above information is true and correct to the best of my knowledge.

Clyde G. Kissinger
Clyde G. Kissinger, President

SUBSCRIBED AND SWORN to before me, this 29th day of April, 1954.

Marlene Job
Notary Public

My Commission Expires:
10-30-57

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 25 T 12 R 22W
BOOK PAGE 25 LINE 1