

8-13

4 060111

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION, S2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,587  
SW NE, SEC. 11, T 10 S, R 21 W/E  
2970 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3007  
Operator: Western Kansas Exploration  
Name & Address P.O. Box 126  
Hays, KS 67601

Lease Name DeYoung Well # 7  
County Graham 125.77  
Well Total Depth 3870 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well XXXXXX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling License Number 4083  
Address Hays, KS

Company to plug at: Hour: 7:00PM Day: 13 Month: August Year: 1990

Plugging proposal received from Jim Manley  
(company name) Western Kansas Drilling (phone) 913-628-2296

Order 215 sxs. 60/40 pos 6% gel and 1/4 floccel per sxs.  
Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXX

Operations Completed: Hour: 7:00PM Day: 13 Month: August Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3810' with 25 sxs. Arbuckle at 3822'  
2nd plug at 1750' with 25 sxs. Anhydrite 1735-1774'  
3rd plug at 960' with 100 sxs. Dakota 655-955'  
4th plug at 260' with 40 sxs. Surface pipe to 207'  
5th plug at 40' with 10 sxs.  
Rathole with 15 sxs.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

SEP 10 1990  
9-10-1990

Remarks: Halliburton Cementing

If additional description is necessary, use BACK of \_\_\_\_\_

I (XXXX) did not observe this plugging.

Signed [Signature]  
(TECHNICIAN)

Herb Deines

INVOICED

DATE: SEP 18 1990

INV. NO. 29361