

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21281-00-00
Spot: NWNE Sec/Twnshp/Rge: 10-25S-9W
380 feet from N Section Line, 990 feet from E Section Line
Lease Name: DILLON Well #: 2-10
County: RENO Total Vertical Depth: 3980 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	228		200 SX
PROD	5.5	3945	2105	150 SX

129.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/09/2009 10:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3780' AND SPOTTED 5 SXS OF CEMENT ON TOP OF SAND. 35 SXS HOT PLUG (ADDED 3% CC TO POS MIX) AT 1407', 1.5 HOURS LATER TAGGED PLUG AT 1250'. SPOTTED 35 SX OF CEMENT @ 833' @ 285' CIRCULATED TO SURFACE WITH 120 SXS OF CEMENT.

Casing Ripped off @ 2105' and plugged through casing as it came out of the hole

Perfs:

Top	Bot	Thru	Comments
3851	3861	CSG	

INVOICED


DATE 1-25-10
INV. NO. 2010060728

Remarks: TICKET 342571 - ALLIED CEMENT CO. OUT OF MEDICINE LODGE, KS 60-40-4% POS MIX

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED

DEC 24 2009

KCC WICHITA

Form CP-2/3

✓JK

PKT