

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21358-00-00
Spot: SESENE Sec/Twnshp/Rge: 10-25S-9W
2310 feet from N Section Line, 330 feet from E Section Line
Lease Name: DILLON Well #: 3-10
County: RENO Total Vertical Depth: 4000 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		190 SX
PROD	5.5	3999	2430	150 SX <u>130.00</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 938-2943

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/10/2009 11:30 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3800' SPOTTED 5 SXS OF CEMENT ON TOP OF SAND. SPOTTED 35 SXS CEMENT HOT PLUG AT 1396' (4% CC) 1.5 HOURS LATER TAGGED PLUG AT 1100'. SPOTTED 35 SXS CEMENT PLUG AT 796'. AT 252' CIRCULATED 140 SXS OF CEMENT TO SURFACE. RIPPED CASING OFF @ 2430' AND PLUGGED THROUGH CASING AS IT CAME OUT OF THE HOLE.

Perfs:

Top	Bot	Thru	Comments
3850	3858	CSG	

INVOICED
DATE 1-25-10
INV. NO. 2010060728

Remarks: ALLIED CEMENT CO. MEDICINE LODGE, KS; 60/40/4% POS MIX - WITH CC IN FIRST SALT PLUG. TICKET #42571

Plugged through: CSG

District: 02

Signed _____

B. J. Hope
(TECHNICIAN)

RECEIVED

DEC 24 2009

Form CP-2/3

KCC WICHITA

SK

PT