

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-30080-00-01
Spot: SW Sec/Twnshp/Rge: 10-32S-38W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: SUGHRUE A Well #: 1
County: STEVENS Total Vertical Depth: 3030 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	611		WITH 550 SX CMT
L1	4.5	2496	721	WITH 50 SX CMT
PROD	5.5	3029	720	WITH 200 SX CMT

98.48

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/17/2009 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Pumping Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/18/2009 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMP 400# HULLS & 25 SX CMT. LOST PILL. 2ND PLUG PUMPED ANOTHER 400# HULLS & 25 SX CMT ON BOTTOM. 3RD PLUG RECOVERED 721' OF 4 1/2" & 720' OF 5 1/2" CASING. RIHWT TO 1700' & LOAD HOLE WITH MUD THEN PUMPED 20 SX CMT IN 5 1/2" CASING. 4TH PLUG PULL TBG TO 650' & PUMPED 50 SX CMT. 5TH PLUG PULLED TBG TO 40' & PUMPED 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2844	2978		

INVOICED
DATE 1-27-10
INV. NO. 2010060731

RECEIVED
DEC 14 2009
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED

DEC - 3 2009

KCC DODGE CITY

Form CP-2/3

PPS