

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20444-00-00

Spot: SENENW

Sec/Twnshp/Rge: 9-17S-27W

990 feet from N Section Line, 2970 feet from E Section Line

Lease Name: HOWARD

Well #: 3

County: LANE

Total Vertical Depth: 4540 feet

Operator License No.: 32457

Op Name: ABERCROMBIE ENERGY, LLC

Address: 150 N MAIN STE 801
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3990		WITH 4 SX CMT
SURF	8.625	285		WITH 175 SX CMT
PROD	4.5	4317	0	WITH 250 SX CMT

147.55

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/20/2009 9:30 AM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: GERALD ACHATZ

Company: ABERCROMBIE ENERGY, LLC

Phone: (620) 793-8186

Proposed Plugging Method: SET CIBP @ TEST CASING. PERFORATE @ 1100' & PUMP 80 SX CMT OVER CASING VOLUME. USE 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: ERIC MACLAREN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/20/2009 2:30 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

PBTD 3990'. 1ST PLUG SET CIBP @ 3990' & 4 SX CMT. 2ND PLUG RIHWT TO 1620' & PUMP 100 SX CLASS A CMT & 3% CC. PULL TBG TO 1100' & REVERSE OUT BALANCE OF CMT. 3RD PLUG TOO H W/TBG, WAIT ON CMT 1.5 HOURS. TEST CASING TO 400#. PERFORATE 4 1/2" @ 1100'. ESTABLISH RATE & PUMP 80 SX CMT, 150# HULLS, & 70 SX CMT. SHUT IN PRESSURE 500#. 4TH PLUG PUMP 50 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 300#. 5TH PLUG TOP OFF 4 1/2" WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4195	4205		L-KC "L"
4155	4162		L-KC "K"

INVOICED

DATE 1-27-10

INV. NO. 2010060729

RECEIVED

DEC 14 2009


Remarks: USED CLASS A CMT & 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC - 3 2009

KCC DODGE CITY

Form CP 2/3