

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20480-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 9-17S-27W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: HOWARD Well #: 4
County: LANE Total Vertical Depth: 4580 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 150 N MAIN STE 801
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3840		WITH 4 SX CMT
SURF	8.625	283		WITH 200 SX CMT 1418.85
PROD	4.5	4301	0	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2009 9:00 AM
Plug Co. License No.: 32457 Plug Co. Name: ABERCROMBIE ENERGY, LLC
Proposal Rcvd. from: GERALD ACHATZ Company: ABERCROMBIE ENERGY, LLC Phone: (316) 793-8186

Proposed Plugging Method: SET CIBP @ 3840' WITH 4 SX CMT. SET HOT PLUG ABOVE CEDAR HILLS, PERFORATE @ 1100', & PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE THEM 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/18/2009 1:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3840' WITH 4 SX CMT. FOUND HOLES IN CASING @ 1540-1786'. RUN TBG TO 1357' & PUMPED 100 SX CMT & 300# HULLS THEN 100 SX COMMON CMT WITH 3% CC. PULLED TBG & WAITED 2 HOURS. PRESSURED TO 500# & HELD. PERFORATE @ 1000' & PUMPED 125 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 400#. TIED ONTO BACKSIDE & PUMPED 70 SX CMT. PRESSURED TO 500#. SHUT IN PRESSURE 500#.

Perfs:

Top	Bot	Thru	Comments
4170	4174		L-KC "K"

INVOICED
DATE 1-27-10
INV. NO. 2010060729

RECEIVED
DEC 18 2009

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

DEC - 3 2009

KCC DODGE CITY

Form C-100